

**STATUS OF MINERAL RESOURCE INFORMATION FOR THE CROW
CREEK INDIAN RESERVATION, SOUTH DAKOTA**

By

Leslie Jane Cox
U. S. Geological Survey

Richard A. Beach
U. S. Bureau of Mines

Administrative Report BIA-73
1980

CONTENTS

SUMMARY AND CONCLUSIONS	1
INTRODUCTION	1
Map Coverage	2
Previous Work	2
GEOLOGY	3
Structure	3
Stratigraphy	3
Water Resources	10
MINERAL RESOURCES	10
Energy Resources	11
Petroleum and Natural Gas	11
Uranium	12
Geothermal Energy	12
Metallic Mineral Resources	13
Manganese	13
Cobalt, Copper, and Nickel	16
Nonmetallic Mineral Resources	17
Sand and Gravel	17
Clay and Shale	18
Zeolites	18
REFERENCES	20

SUMMARY AND CONCLUSIONS

Identified (known) mineral resources on the Crow Creek Indian Reservation include sand and gravel, manganese, and clay and shale. Only sand and gravel has been produced commercially.

An estimated 300 million cubic yards of sand and gravel remains in five large terrace deposits along the Missouri River on the reservation. Development of this resource is directly related to the demand for sand and gravel for local construction projects. Recovery of part of the sand and gravel may be hampered by the competing use of terraces as irrigation land.

More than 1.7 million tons of metallic manganese are in low-grade deposits in the DeGrey Member of the Pierre Shale and in terrace deposits on the reservation. The geology and methods of mining and processing this subeconomic mineral resource have been studied extensively; technologically, extraction of manganese is possible. However, development of this resource is unlikely barring a national emergency or manganese prices that are many times higher than at present. Moreover, an efficient, economical method to separate manganese-bearing nodules from the shale or gravel host rocks has yet to be found.

Substantial amounts of clay and shale occur in the Pierre Shale on the reservation; probably some of these materials are suitable for making brick or other structural clay products and lightweight aggregate. Detailed geologic and economic feasibility studies would be needed to determine if these resources can be developed profitably.

Undiscovered mineral resources that may occur on the reservation are natural gas, petroleum, and

geothermal energy. Moderate potential exists for discovery of limited flows of natural gas for local use, but little potential is indicated for development of petroleum or low-temperature (warm water) geothermal resources.

Occurrences of zeolites and of very low-grade oil shale and uranium, all in the Sharon Springs Member of the Pierre Shale, may point to future mineral resources on the reservation.

INTRODUCTION

This report was prepared for the U.S. Bureau of Indian Affairs (BIA) by the U.S. Geological Survey (USGS) and the U.S. Bureau of Mines (USBM) under an agreement to compile and summarize available information about the geology, mineral resources, and potential for economic development of certain Indian lands. Source materials were published and unpublished reports and personal communications. There was no fieldwork.

The Crow Creek Indian Reservation, which includes parts of Buffalo, Hughes, and Hyde Counties, lies along the left bank of the Missouri River in south-central South Dakota. In general, it is bounded on the southwest by Lake Francis Case and by Lake Sharpe, main stem reservoirs on the Missouri, and on the east and north by north-south and east-west lines of survey ([Figure 1](#)). The reservation comprises 127,152.74 acres: 62,434.91 acres are tribally owned, 64,677.83 acres are individual allotted lands, and 40.00 acres are government land (U.S. Bureau of Indian Affairs, 1979). According to BIA, the population of the reservation in 1979 was estimated at 1,744; Fort Thompson, the tribal headquarters, and Stephan are

the only communities on the reservation. Larger cities or towns in the region include Pierre (population 9,699, 1970 Census) and Chamberlain (population 2,626, 1970 Census).

Commercial air transportation and train service are available at Pierre, the State capital, about 50 miles northwest of the reservation. Bus and truck service is available at Chamberlain, 10 miles south of the reservation. Surface transportation is via hard-surfaced, all-weather State Highway 34, which traverses the reservation from east to west, and State Highway 47, which runs north-south. Numerous graveled and graded secondary roads also serve the area.

The topography of the reservation consists of high rolling upland on the north and east that gives way to deeply eroded badlands and terraces along the Missouri River valley (Howells, 1974). Elevations range from 1,350 feet above sea level on the shore of Lake Francis Case to slightly over 2,000 feet at the north edge of the reservation. In this region the climate is rigorous, and precipitation averages 17 inches per year. Owing to rugged topography or poor soils, most of the reservation is rangeland used for grazing, but some of the terraces and lowlands along the Missouri have been developed for irrigation.

Map Coverage

The entire reservation has been mapped at several scales of detail, both topographically and geologically.

Recent topographic maps that include the whole reservation are the Huron and Mitchell sheets of the United States 1:250,000-scale series,

published by USGS. At a larger scale, recently published maps in the Survey's 7½-minute quadrangle series provide detailed coverage of all but the southeastern tip of the reservation at a scale of 1:24,000; that tip is shown on an older 15-minute quadrangle map at a scale of 1:62,500 (Figure 2).

Geologic maps at a scale of 1:62,500, published by the South Dakota Geological Survey, portray the geology of most of the reservation (Curtiss and Waddel, 1951, 1951a; Petsch and Fairbanks, 1952; Petsch and others, 1950, 1950a). More recently, Howells (1974) has mapped the surficial geology of the entire reservation (scale 1:125,000).

Previous Work

Although many reports, dating from before the turn of the century, allude to the geology or mineral resources in the vicinity of the reservation, interest was first focused on manganese resources in the region in the years shortly before, during, and just after World War II. The result was a series of publications, mostly by USBM and the South Dakota Geological Survey, about the manganese resource and how it might be mined and processed; the work is described in detail in a subsequent section of this report.

The first comprehensive report specifically about mineral resources of the reservation (and the Lower Brule Indian Reservation adjacent to it) was prepared by Henkes and Gries (1963, 42 p.). The present study, designed to bring that report up-to-date, necessarily borrows much from it.

Publications of three groups stand out among numerous sources of information about the geol-

ogy and mineral resources of the Crow Creek Reservation: South Dakota Geological Survey, USGS, and USBM. These agencies are the prime sources of data on mineral resources of the reservation.

GEOLOGY

The reservation is in the Missouri Plateau section of the Great Plains physiographic province (Fenneman, 1931; Flint, 1955). It lies in a transitional area in which the thick lenses of sedimentary rocks of the Williston basin to the northwest meet the resistant Precambrian Sioux Quartzite ridge to the east (Figure 3). Paleozoic and older Mesozoic formations thin eastward from the basin and pinch out against the Sioux uplift. Thus approximately 1,500-2,000 feet of sedimentary rocks, mostly Cretaceous in age, overlie the folded Precambrian basement.

The flat-lying Pierre Shale forms the bedrock under virtually all of the reservation. Unconformably covering that shale unit are Cenozoic sediments largely resulting from Pleistocene continental glaciation which is also responsible for shaping the high rolling upland topography of the area. Erosion has cut deeply into the upland near the deep meandering trench of the Missouri River and forms a badlands area known as the "breaks" (Howells, 1974).

Structure

The reservation lies between two of the large structural features of South Dakota: the Precambrian Sioux Quartzite ridge to the east and the

Lemmon syncline to the west (Figure 3). The resistant quartzite ridge extends westward toward Chamberlain from the vicinity of Sioux Falls. It plunges gently to the west and probably extends beneath the reservation. The general regional picture of the Precambrian surface is a broad, flat terrace about 60 miles wide that slopes westward into the Lemmon syncline at a rate of 1 or 2 feet per mile.

Locally, the principal structure of the exposed bedrock is a northwest-trending "high" extending from west of Chamberlain to slightly west of the Big Bend of the Missouri River. The structure has not been delineated precisely because of limited outcrop; however, a 1940 magnetometer study shows a "high" trending along the same northwest path (Wing and Gries, 1941, p. 67).

Structure is a major consideration in prospecting for oil and gas, but in this area the structure of potentially oil bearing formations at depth is not necessarily reflected in the surface beds. Many of the formations present in the Lemmon syncline thin and pinch out toward the east and eventually extend onto and overlap the folded surface of the Sioux Quartzite ridge (Wing and Gries, 1941). The fold in the Cretaceous overlap at Chamberlain is the Medicine Butte anticline (Petsch, 1946).

Stratigraphy

Descriptions of the rock units underlying the reservation are summarized in a generalized stratigraphic column (Table 1). Information on bedrock older than Upper Cretaceous is limited to the few wells in the area that have been drilled deeper than the Newcastle (Dakota) Sandstone and to correla-

tion with the well-known succession of pre-Cretaceous rocks in western South Dakota. At one time Tertiary formations covered much of South Dakota but have since been removed by erosion. A simplified geologic map ([Figure 4](#)) shows the distribution of Quaternary sediments, the widespread Cretaceous Pierre Shale, and the limited outcrop of the Niobrara Formation along the Missouri River.

TABLE I
Stratigraphic Section, Crow Creek Indian Reservation

System and Series	Unit-Group, Formation, Member	Maximum Thickness (feet)	Character and Distribution
Quaternary Recent	Alluvium	185	Water-laid deposits consisting of clay, silt, sand and some gravel; occupies flood plains, bars, islands, and other channel features of the Missouri River and its tributaries. The youngest alluvium has been deposited by present streams, but alluvial deposits have been accumulating in the Missouri Valley since the Pleistocene Epoch. The underlying valley fill and higher terraces have been deposited in part by melt water from Pleistocene glacial ice. Deposits may reach 185 feet (Howells, 1974; Petsch, 1946).
	Dune Sand		Wind-blown and -sorted deposit of mostly rounded quartz sand, often grass-stabilized.
Pleistocene			During the Pleistocene Epoch, ice sheets advancing from the east greatly modified the topography and drainage of South Dakota and established the course for the present Missouri River. The earliest ice apparently extended west of the river but later ice advanced only to its eastern bank. A mantle of glacial drift, the material eroded from the surface over which the glaciers moved, was left on the surface as the ice retreated.
	Loess	100	Air-sorted and -deposited drift consisting of unconsolidated, well-packed, buff-colored silt to fine sand with some clay and medium sand. A thin coat of loess overlies most of the area. Deposits reach 100 feet in thickness. Those less than 5 feet thick are not shown on Figure 4 (Howells, 1974; Petsch, 1946),
	Glacio-fluvial (Outwash)	30	(Outwash) - Water-sorted drift consisting of mixed sand and gravel. Located in dissected terraces of the Missouri River and its tributaries.
	(Terrace)	100	(Terraces) - Fairly level areas of alluvium located above the present flood plain. Ter-

Status of Mineral Resource Information for the Crow Creek Indian Reservation, South Dakota
Leslie Jane Cox and Richard A. Beach

			<p>racess are remnants of the former Missouri River valley, left behind as the river channel deepened during torrential flooding due to the melting glaciers. There are 3 types of terrace materials: glacial gravels consisting of hard materials such as granite, quartzite, veinquartz, flint, chert, and gneiss; light gray and bluish gray chalc-dony and limestone pebbles carried by streams from the west; local shale and iron carbonate fragments (Rothrock, 1944). Younger terraces and alluvium derive material reworked from older terraces. Deposits are more than 100 feet thick in places (Petsch, 1946; Rothrock, 1944).</p>
	(Colluvium)	30	<p>(Colluvium-Alluvium) - Heterogeneous mix-tures of water- laid and slumpage detritus of terrace material and Pierre shale frag-ments. Commonly found at the base of steep slopes. As much as 30 feet thick (Howells, 1974).</p>
	Glacial Moraine	130	<p>Ice-deposited, undifferentiated drift; mostly clay, silt, and sand; ranges up to boulder in size. Characterized by swell and swale topography, less than 20 feet of re-lief, and underdeveloped drainage. As much as 130 feet thick and generally loess cov-ered. Drift that was deposited beneath the continental glaciers is called ground mo-raine while drift deposited at their margins is end moraine. Both ground and end moraine are shown as glacial moraine in Figure 4 for simplicity (Howells, 1974; Curtiss and Waddel, 1951; Petsch and others, 1950a).</p>
Upper Cretaceous	Pierre Shale	370	<p>Dark gray, fissile, carbonaceous, marine shale; contains several zones of bentonitic beds and concretions; weathers to yellowish gumbo.</p>
	Mobridge Member	20	<p>Succession of bluish-gray calcareous shale and chalk beds containing small, flat, lime-stone concretions and a few bentonite lay-ers. Weathers to shades of light to brownish buff and is largely responsible for the buff and yellow subsoils of the region (Searight, 1937; Curtiss and Waddel, 1951a; Petsch and others, 1950a).</p>
	Virgin Creek Member	120	<p>Upper Virgin Creek: Noncalcareous, medium gray to yellowish bentonitic shale. Weathers readily to gumbo. Within the topmost shale are gray to buff cylindrical concretions and small bluish-gray limestone nodules contain-ing the fossil remains of small crabs. The high topographic position of the member in the valley breaks has subjected it to exten-sive erosion and consequently limited the outcrop and exposure.</p> <p>Lower Virgin Creek: Relatively resistant dark gray shale and numerous thin (less than 2 inches thick) bentonite beds. The shale weathers to thin gray flakes with a sub-metallic appearance Small barite rosettes</p>

Status of Mineral Resource Information for the Crow Creek Indian Reservation, South Dakota
Leslie Jane Cox and Richard A. Beach

Verendrye Member	50	<p>occur near the base. The Lower Virgin Creek is approximately 50 feet thick and the entire member is less than 100 feet thick in this area (Searight, 1937; Curtiss and Waddel, 1951a; Petsch and Fairbanks, 1952). Gray to brownish gumbo-forming shale which contains many layers of large, flat, iron--manganese carbonate concretions. The concretionary layers are generally 6 inches or less in thickness and reach several feet in diameter. Typically the concretions have gray to green interiors and purplish-black surfaces. The basal 47 feet of the Verendrye Member appears as a banded outcrop of alternating beds of light gray fissile shale and dark gray gummy shale. Within these layers are intermittent zones of large white to gray rusty limestone concretions. Mostly basal beds are exposed as outcrop on the reservation (Wing and Gries, 1941).</p>
DeGrey Member	85	<p>Upper DeGrey: Succession of highly bentonitic gray shale and clay alternating with grayish yellow bentonite and persistent to intermittent layers of concretions. All of the beds range from less than an inch to less than 2 feet in thickness. The zone is characterized by the presence of abundant black iron-manganese carbonate concretions which form a conspicuous black band of outcrop running parallel to the river. The shale weathers to gumbo but the concretions weather out in relief and accumulate on the surface. The concretions are 1-4 inches thick and 3-8 inches in diameter. In many places they form beds as much as 8 inches thick and 10 feet long. The color of fresh nodules ranges from pale gray to olive--green. Weathered surfaces are black (Wing and Gries, 1941; Searight, 1937). Traceable bentonite beds include: The Lower Micaceous Bentonite (LMB) - a 1- to 6-inch yellow bentonite with abundant biotite flakes that consistently occurs at the base of the concentration of the iron-manganese concretions. The Big Bentonite Bed (BBB) - an 8-inch bentonite separated from an underlying 1-inch bentonite by 2 inches of shale. The Upper Micaceous Bentonite (UMB) is found 5 to 10 feet above the BBB. Two or all three beds are typically present in an outcrop (Wing and Gries, 1941).</p> <p>Lower DeGrey: Light gray bentonitic clay and siliceous shale containing noticeably fewer concretions and bentonites than the upper DeGrey. Every exposure shows three prominent 4- to 6-inch bentonite beds, with or without additional thin beds. The lower DeGrey thickens rapidly to the north and west, increasing from 30 to 50 feet. The upper 12 feet in the thickest sequence contain no concretions whereas concretions are persistent throughout the basal beds. The thickness of the entire member ranges from 42 to</p>

Status of Mineral Resource Information for the Crow Creek Indian Reservation, South Dakota
Leslie Jane Cox and Richard A. Beach

		84 feet (Wing and Gries, 1941; Searight, 1937; Curtiss and Waddel, 1951a; Cox and others, 1962; Crandell, 1950).
Crow Creek Member	15	Very light gray foraminiferal marl underlain by a 1-foot layer of a uniform, persistent, basal brown, silty sandstone that often appears to be a sandy or silty limestone. The Crow Creek weathers to a yellow soil which supports abundant growth of yucca plants. In places it is as much as 14 feet thick (Wing and Gries, 1941; Cox and others, 1962; Curtiss and Waddel, 1951a; Petsch and others, 1950a).
Gregory Member	84	Alternate beds of dark gray, noncalcareous shale containing brown limonitic concretions, and light gray to buff calcareous layers. The calcareous layers range from slightly calcareous shale to impure chalk and range from a few inches to several feet in thickness. An intermittent chalky bed occurs a few feet below the top of the member near the mouth of Crow Creek. Abundant brown, fossiliferous concretions range from 2 to 6 inches in thickness and are either small and intermittent or form nearly continuous ledges. Within the concretions are numerous large specimens of Inoceramus and Baculites. A layer of septarian concretions about one foot in diameter lies 37 feet below the top. Altogether the member ranges from 40 to 84 feet in thickness (Wing and Gries, 1941).
Sharon Springs Member	15	Hard, fissile, dark gray to black bituminous shale speckled with fish scales, various twig-like particles and bone splinters. A very thin zone of small white concretions sometimes appears at the top of the fish scale zone. The lower portion generally contains many bentonite layers that are ½ inch to 1 foot thick. A bed of impure, rusty selenite appears at the contact with the underlying Niobrara Formation. Uranium content averages approximately 0.0015 percent for the entire member (Kepferle, 1959). Uranium-rich zones lie just above the uppermost thick bentonite bed or disconformably above the Niobrara chalk in the absence of bentonite. The uranium is held in the phosphatic fossil fish and carbonized plant remains. The member also contains a suite of trace elements in which arsenic, boron, chromium, copper, molybdenum, nickel, selenium, and vanadium are conspicuous (Tourtelot, 1956). The Sharon Springs is approximately 15 feet thick (Curtiss and Waddel, 1951; Petsch and Fairbanks, 1952; Wing and Gries, 1941).
Niobrara Formation	200	Crops out as vertical cliffs of light colored chalk along the Missouri River below Big Bend Dam. Physically amorphous, consisting of foraminiferal and flocculent material. Impurities include clays, organic

Status of Mineral Resource Information for the Crow Creek Indian Reservation, South Dakota
Leslie Jane Cox and Richard A. Beach

matter, and a small amount of iron sulfide in the form of pyrite pellets. Unweathered chalk is predominantly very dark gray to black. Weathers to buff and bleaches to white near the surface (Rothrock, 1931; Petsch, 1946).

THE NIOBRARA IS THE OLDEST OF THE ROCK UNITS EXPOSED ON THE RESERVATION.

	Carlile Shale	140-325	Light-blue or light-gray to black shale, generally noncalcareous; contains one or more sandstone or sandy intervals in the top half. Marine (Howells, 1974).
	Greenhorn Limestone	50-100	Buff to bluish, white, or gray, highly calcareous shale; commonly marly and fossiliferous. May be interbedded with thin limestone layers. Marine. (Howells, 1974).
	Graneros Shale	150-320	Medium to dark-gray noncalcareous shale. Calcareous concretions and pyrite and marcasite crystals common. Locally the formation may contain thin lenses and beds of sandstone and may be sandy or silty at the base. Along the crest and slopes of the Sioux uplift, basal beds of sandstone or sandy and silty shale may exceed 100 feet in thickness. Marine. (Howells, 1974).
Lower Cretaceous	Newcastle Sandstone	280-350	White, tan, or light-gray sandstone, very fine to coarse-grained, loose to tightly cemented; interbedded with dark-colored shale. Deltaic or near-shore deposits. (Howells, 1974).
	(the Dakota Sandstone of some authors [Darton, 1951])		
	Skull Creek Shale	0-130	
	Inyan Kara Group	0-80	Dark bluish-gray shale. Marine. (Howells, 1974).
	(includes Fall River Sandstone [the Dakota Sandstone of most previous reports] Fuson Shale, Minnewaste Limestone, and Lakota Sandstone [Darton, 1951])		
			White to light-gray or tan sandstone, fine to medium-grained; contains beds of gray to black and reddish to buff shale and siltstone. Continental to marginal marine deposits (Howells, 1974).
Jurassic	Sundance Formation	0-90	White, buff, dark-pink, or red sandstone, medium to fine-grained; may be glauconitic in some areas; contains layers of red to brown, green, and gray shale. Marine (Howells, 1974).
Permian and Pennsylvanian	Minnelusa Formation	0-250(?)	White to yellow, buff, or red sandstone interbedded with anhydrite, brick-red to orange, green, or black shale, and white to brown to gray limestone and dolomite. Continental to marine (Howells, 1974).
Mississippian	Madison Group	0-100(?)	
	(Pahasapa Limestone and Englewood		

Status of Mineral Resource Information for the Crow Creek Indian Reservation, South Dakota
Leslie Jane Cox and Richard A. Beach

	Limestone [Darton, 1951])		White to tan, brown, and gray limestone and dolomite. Locally may contain shale or anhydrite beds. Marine (Howells, 1974).
Devonian	Undifferentiated	0-50(?)	Red, green, gray, and black shales interbedded with anhydrite, red to gray, medium to fine-grained sandstone and siltstone, and gray to brown limestone and dolomite. Marine (Howells, 1974).
Transgressive	"basal wash"	0-50	White and buff to pink to light reddish purple sandstone, generally coarse-grained but ranges from fine-grained to gravelly. May be arkosic. Reflects the lithology of underlying or nearby Precambrian rocks. This is a coarse clastic facies that overlies the Precambrian surface throughout much of South Dakota (Howells, 1974).
Precambrian	Sioux Quartzite	?	Pale maroon,-pink, red or purple, hard, dense, orthoquartzite. Locally white, locally friable. Contains a few beds of catlinite (pipestone) (Howells, 1974).
	Igneous and metamorphic rocks	?	Various colored granite, gneiss, schist, and other igneous and metamorphic rocks (Howells, 1974).

The Pierre Shale underlies most of South Dakota west of the Missouri River and is widespread beneath the glacial drift east of the river. Exceptions include the Black Hills and restricted areas of the Missouri River Valley where the formation has been removed by erosion (Searight, 1937). In the Missouri River Valley, the Pierre Shale is a thick body of shale and clay that has been divided into eight members. From the base up these include the Sharon Springs, Gregory, Crow Creek, DeGrey, Verendrye, Virgin Creek, Mobridge, and Elk Butte Members. With the exception of the Elk Butte, all of the members crop out on the reservation. The total thickness of the Pierre is as much as 370 feet on the reservation.

"The shale commonly contains 65-80 percent clay minerals, 15-25 percent

quartz, a few percent feldspar, and small amounts of calcite, dolomite, biotite, pyrite, gypsum, jarosite, clinoptilolite, and organic matter. Cristobalite is abundant in many but not all siliceous shales. Typically, the clay-mineral fraction contains about 5 percent each of kaolinite and chlorite, 15 percent illite, 35 percent montmorillonite, and 40 percent mixed-layer illite-montmorillonite. Principal variations from this average composition are: (1) a more montmorillonitic phase that comprises the frothy-weathering units, and (2) a montmorillonite-poor phase, commonly with unusually large amounts of kaolinite and no chlorite, mainly in the lower part of the Pierre shale. Almost all bentonite beds

of the Pierre are composed largely or exclusively of montmorillonite, rarely a little kaolinite, variable but usually small amounts of feldspar and biotite, and little or no quartz; the most abundant mineral in a few bentonite beds near the base of the Pierre shale is clinoptilolite" (Schultz, and others, 1960, p. 2041).

Water Resources

"Shallow ground water is not obtainable in much of the area and where it is found, it often is of poor quality. Surface water, with the exception of the Missouri River reservoirs, though a valuable and widely distributed resource, is undependable because of scanty and erratic precipitation. Therefore, some people have drilled deep artesian wells for their basic water needs. Because of the expense of drilling artesian wells, most people will continue to use surface water and shallow ground water, as available, particularly for livestock supplies.

"The best chemical quality and largest volume supply of water available within the reservations is from the Missouri River reservoirs. Development of some of the more than 17 million acre-feet of annual flow in the Missouri appears to be an attractive solution to water shortage and a boon to economic improvement, particularly for irrigation. However, financial cost of such development probably will restrict it to large projects or to individual users

within a mile or so of the reservoirs; in general, the greater the distance from the reservoir, the higher the cost and the larger the area that probably should be developed.

"Surface runoff is widely developed for livestock supplies. Although, evaporation losses are high, as much as 38 inches a year, dams and dugouts are a comparatively inexpensive way to hold snowmelt and storm runoff for later use at widely dispersed sites. Use of this type of water resource will continue to grow because of its many advantages.

"Shallow ground water of fairly good quality is available in only a few areas. In most of these areas well yields will be less than 20 gpm, although two areas will support well yields greater than 50 gpm. Most future development of shallow ground water probably will be for stock and domestic wells in the few favorable areas. Water quality, of great importance in considering any possible source of supply, is of particular concern for shallow wells because of the ease of pollution from surface sources, possible high nitrate, and the known possibility of high selenium content." (Howells, 1974).

MINERAL RESOURCES

The following sections summarize available information about energy, metallic, and nonmetallic mineral resources that occur, or that may possibly occur, within the Crow Creek Indian Reservation. The commodities discussed include identified

as well as undiscovered mineral resources, according to the classification adopted by the U. S. Bureau of Mines and the U. S. Geological Survey (1980).

Aside from small amounts of manganese--bearing nodules produced from terrace gravels near Fort Thompson in the course of experiments to recover manganese, mineral production from the reservation has been limited to sand and gravel.

There are no leases or permits for oil and gas or for other minerals on Indian tribal trust or allotted lands on the reservation (U. S. Bureau of Indian Affairs, 1979a). Recently, however, companies have indicated interest in obtaining oil and gas leases if they should be offered.

Energy Resources

Petroleum and (or) natural gas, uranium, and geothermal energy resources conceivably may occur on the reservation, although they are not known there now. Very low-grade oil shale occurs in the Sharon Springs Member of the Pierre Shale; a few thin beds may yield up to 8 gallons of oil per ton (Kepferle, 1959, p. 581; Swanson, 1960, p. 19). Development of oil shale on the reservation is unlikely.

Petroleum and Natural Gas

No oil or gas wells have been drilled on the reservation. Several exploratory or wildcat wells have been drilled, however, to the south, west, and north of the reservation (Petroleum Information Corp., various dates); all were dry holes.

Natural gas has been produced from artesian water wells in central and eastern South Dakota for many years. According to Henkes and Gries (1963, p. 16),

"Numerous artesian water wells drilled in the vicinity of the Missouri River have produced natural gas along with the water. In a few cases this gas is produced from the Niobrara shale, but most comes from the Dakota sand. The quantity of gas is small and generally is allowed to flow into the air or is burned as a flare; some farmers and ranchers, however, have piped the gas into their homes and used it for heating and cooking. Gas was found in an artesian well drilled in 1893 at the Pierre Indian School at the east edge of Pierre, but it never was used and the well was plugged in 1939 (Gries, 1940).

"In 1894, a hotel in Pierre drilled a water well to 1,300 feet where a strong flow of water and gas was obtained. The volume of gas was sufficient for cooking and for heating and lighting the hotel, and a surplus was piped to another company. In the same year, the city of Pierre drilled a water and gas well that produced enough gas to supply practically every home and business house in the city for cooking, heating, and lighting. All streets in the city were lighted by gas lights. Subsequently, five more wells were drilled for gas. Only one, drilled in 1910 at the State capitol, reported any specific gas quantity or pressure; this well initially produced 84,960

cubic feet per day at a pressure of about 165 psi, but by 1916 production had diminished to about 15,100 cubic feet per day at 30 psi. No cumulative gas production figures are available, but in 1930 one well had an indicated annual production of 14,000,000 cubic feet (Gries, 1940)."

Recent studies indicate that the potential for natural gas from shallow, porous, low-permeability reservoir rocks, such as some chalks, sandstones, and siltstones of Cretaceous age in the Great Plains, is more significant than was formerly thought (Rice and Shurr, 1978, p. 891-892; 1980, p. 969-987; Scholle, 1978, p. 892; Shurr and Rice, 1979, p. 256). Near the Sioux uplift, moreover, these rocks show facies changes and local unconformities that may influence natural gas accumulation. Improvements in logging and well-completion techniques also enhance the potential for natural gas production from these rocks.

While several factors lessen the prospects for discovery of oil or gas on the reservation (Henkes and Gries, 1963, p. 17; Miller, 1971, p. 706-717), the area does have some potential for oil and, especially, for natural gas. Production of limited quantities of gas from the nearby Pierre gasfield, coupled with a very low density of exploratory drilling, possible favorable structure (Petsch, 1942), and substantially higher prices for oil and gas, indicate that further exploration for these commodities is warranted. Moreover, contrary to earlier opinions, recent mapping by Howells (1974) shows that favorable Paleozoic formations underlie at least part of the reservation.

Wells, including water wells, drilled to the Niobrara or deeper should be tested carefully for gas production. Even though the output may be small, flows of gas sufficient for local use may be obtained.

Uranium

Investigations by Tourtelot (1956), using surface exposures and gamma-ray logs of holes drilled for oil, showed that the Sharon Springs Member of the Pierre Shale is radioactive in the subsurface of southern South Dakota. At a road cut near Oacoma, he found thin beds of shale containing as much as 0.01 percent uranium. Additional work by Kepferle (1959) confirmed that the Sharon Springs Member is anomalously rich in uranium over a wide geographic area in South Dakota and northeastern Nebraska. However, uranium in the Sharon Springs is too low in grade to be recovered commercially at present.

Although the potential for discovery of uranium ore deposits on the reservation seems low, local concentrations of uranium may exist either in the Sharon Springs or in other favorable sedimentary horizons.

Geothermal Energy

The reservation is on the fringe of an area in south-central South Dakota where thermal gradients measured in wells and test holes are generally above normal and where some wells may produce low-temperature geothermal water from the Dakota Sandstone (Adolphson and LeRoux, 1968; Schoon and McGregor, 1974). Such warm waters may

have a potential use in space heating and agriculture on a local basis. Insufficient data are available to determine the significance of this resource on the reservation.

Metallic Mineral Resources

Large deposits of low-grade manganese resources are pre-eminent among metallic mineral resources on the reservation. Iron occurs with the manganese, but it would be recovered only as a byproduct of manganese production. Several authors have mentioned the Pierre Shale as a possible non-bauxitic source of aluminum (Gries, 1942, p. 64-66; Rothrock, 1944, p. 65-66; Miller, 1959, p. 26). However, many alternate non-bauxitic sources of aluminum exist elsewhere and are far more promising.

Manganese

Interest in the vast resources of low-grade, manganese-bearing material in the Pierre Shale along the Missouri River below Pierre has risen and fallen in the 50-year period since their discovery. For a concise overview of the history, geology, mining, and beneficiation of these deposits, the following information is taken from Gries (1975, p. 107-108).

"History of exploration.--Concretions that weather out of the DeGrey Member of the Pierre Shale form a continuous black band along the Missouri River breaks in central South Dakota. Mr. Albert Amundsen of Lake Andes, S. Dak., discov-

ered in 1927 that these concretions, or nodules, were unusually high in manganese. This aroused the interest of John A. Savage Co., of Duluth, and of Mr K. M. Leute of Minneapolis, who sponsored a program of test pitting and sampling of the manganese-bearing beds both north and south of Chamberlain. D. F. Hewett of the U. S. Geological Survey analyzed this test pit data and concluded that the manganese concretions underlying 9 townships near Chamberlain contained an estimated 102,000,000 tons of metallic manganese (Hewett, 1930).

"Stratigraphic studies in 1934-35 indicated that the manganese-bearing zone formed a laterally continuous member of the Pierre Shale formation, and a systematic program of section measuring, mapping, trenching, and sampling was conducted by the South Dakota Geological Survey in 1940 and 1941 (Gries and Rothrock, 1941).

"The U. S. Bureau of Mines inaugurated an extensive evaluation of the manganese deposits of the Missouri Valley in 1940. A pilot plant was built on the outcrop 8 miles west of Chamberlain in 1941. Experiments in mining and transportation of concretion-bearing shale, and in separating nodules from shale, continued from 1941 to 1947 (Pesonen and others, 1949; Zinner and Grosh, 1949).

"In the late 1950's the Pittsburgh Pacific Co. became interested in the concentration of manganese nodules in terrace

gravels along the Missouri River north of Fort Thompson, Buffalo County. An experimental plant was built to devise methods of separating the gravel into (1) a manganese nodule concentrate, (2) gravel, and (3) waste substances.

"Description of the deposits.--The DeGrey Member consists of dark gray shale, numerous thin bentonite beds, and abundant iron-manganese concretions. It is underlain by the thin, light-colored marl of the Crow Creek Member, and overlain by the dark, gumbo-forming shale of the Verendrye Member.

"The nodules occur in distinct layers parallel to the bedding of the enclosing shale. The average nodule has the size and shape of a large potato. Nodules may be widely separated or so closely spaced as to form a nearly continuous pavement. The Bureau of Mines has recognized three types of concretions: (1) hard concretions having a hardness of 4.0 to 5.0 on Moh's scale, which are the most abundant, (2) soft concretions that have a hardness of 2.5 to 3.5 and that may be soft throughout or may have a hard core and (3) still softer nodules that grade into shale and are as likely to have fractures going through a concretion as around it. Types 1 and 2 easily break free of the enclosing shale.

"Fresh unweathered concretions of the hard variety are medium gray to olive. Weathered nodules have a gray center surrounded by a rusty brown halo and a purplish-black outer crust. The soft variety-

ies are ordinarily white to cream colored when fresh and light brown after weathering. The concretions are mostly carbonates of manganese, iron, calcium, and magnesium. The non-carbonate constituents are mainly silica and alumina, probably present in the form of clay. A typical nodule contains 14 to 17 percent manganese and 6 to 10 percent iron.

"The Bureau of Mines conducted an intensive sampling program along both sides of the Missouri River from T. 102 N. to T. 107 N., and up the White River as far as T. 104 N., R. 74 W. The concretion zone ranged in thickness from 12 feet at Wheeler Bridge, Charles Mix County, to 72 feet near the Big Bend of the Missouri River. The average thickness used in tonnage estimates was 40 feet. Samples from bucket drill holes were dried and hand sorted to separate the concretions from the shale. Concretions range from 2.45 percent by weight near Big Bend to 6.11 percent near Oacoma, Lyman County; the average, over all areas drilled, is 4.85 percent of the dry material in the zone. If minus one-half inch material is excluded, the percentage drops to 3.19.

"The average composition of concretions in 9 of the 10 areas drilled is 15.68 percent manganese and 8.7 percent iron. For the plus one-half inch concentrate, the percentages increase to 16.09 and 10.26 respectively.

"Experimental mining indicated that the concretion zone could be mined in a

single bench, using a 3-yard or larger shovel. Mining and hauling would be difficult in periods of continued wet weather.

"A two- or three-stage wet jigging process appeared to be the most satisfactory method of separating the nodules from the shale. Methods that resulted in a shale-free concentrate yielded an appreciably smaller percentage of the total manganese than methods that permitted a small percentage of shale to remain in the concentrate. Zinner and Grosh (1949) noted that it would be desirable to devise a metallurgical process that could handle a concentrate with no less than 10 percent shale."

The literature about manganese deposits of the Missouri Valley is extensive. It may be divided into reports primarily about (1) the geology and distribution of the manganese-bearing rocks, (2) mining and beneficiation (concentration) of the resource, and (3) metallurgical processing of a manganese nodule concentrate. Few of these studies concern deposits on the Crow Creek Reservation specifically, but many are applicable to the manganese resources there nonetheless.

Compared with other domestic manganese resources, the Missouri Valley deposits are large but very low in grade. Pesonen and others (1949, p. 87) calculated "that an outcropping and lightly covered manganiferous zone 523 miles in peripheral length and 365 feet wide contains approximately 12,000,000 tons of manganese in 77,700,000 tons of concretions. . . "

Of the 523 miles of outcrop, Henkes and Gries (1963, p. 23) estimated that about 14 percent, or 73 miles, lies within the limits of the Crow Creek Reservation and that 1.7 million tons of manganese is contained therein. Manganese resources in the DeGrey Member were mapped by Gries and Rothrock (1941), Rothrock (1943), and Pesonen and others (1949). [Figure 1](#) shows the approximate location of these deposits on the reservation. Detailed sampling would be needed to accurately determine the extent and grade of manganese resources on the reservation.

Additional manganese resources are in terrace gravels near Fort Thompson. These deposits were investigated by the Pittsburgh Pacific Co. (1961) who thought the manganese nodules might be separated from the gravel more easily than from the shale. Based on limited sample data, the company (1961, p. 15, 18) estimated that the 8,000-acre terrace contains about 600 million tons of manganiferous gravel with 6 million tons of manganese. However, the company's efforts to separate the nodules from the gravel were only partly successful.

Two reports summarize extensive work by USBM on mining and beneficiating the Missouri Valley manganese deposits in the DeGrey Member (Dupuy and others, 1946; Zinner and Grosh, 1949). Briefly, they found that mining and processing a full thickness of the manganese bearing zone probably would be required to sustain large-scale commercial operations. The nodules in this material would be notably more difficult to concentrate than altered or weathered nodules in surficial deposits. Wet jigging methods showed the most promise in treating the fresher material, but the

jigging tests still did not produce a clean nodule concentrate, yield a high-grade product, or recover most of the manganese (Zinner and Grosh, 1949, table 7).

Metallurgical studies (Knickerbocker and Miller, 1942; Jacobs and Hunter, 1946; Torgeson and others, 1946) are pertinent only because they show that it is technically feasible to produce manganese metal, ferromanganese, or other commercial products using raw materials from the Missouri Valley deposits, and because they indicate specifications required of the beneficiated product for various metallurgical processes.

The conclusions of Henkes and Gries (1963, p. 25) regarding manganese resources on the reservation appear to be valid today:

"At present there is no market for the manganese nodules. It is technically possible to use the nodules directly in the production of basic pig iron, or to produce manganese metal by an electrolytic process. Neither use is economically feasible at present. Manufacture of ferromanganese by complex pyrometallurgical processes, or recovery of manganese by leaching and chemical processes is also technically possible, but completely uneconomic in the foreseeable future.

"Barring a national emergency, the prospects for developing manganese from the Pierre shale are remote. The greater accessibility of the outcrops in the Chamberlain-Oacoma area suggest that when development does come, it will be in that area. With the tremendous tonnages avail-

able close to the railroad, development would be slow to extend far to the north or south."

A comprehensive, authoritative report about the recovery of manganese from low-grade domestic resources, which places the Missouri Valley deposits in a national perspective, ranks these deposits far down on the list (National Materials Advisory Board, 1976, p. 17, 54-55). This report and a recent commodity profile on manganese by USBM (DeHuff and Jones, 1979, p. 7) both paint a similar pessimistic picture for development of the Missouri Valley deposits.

Manganese deposits on the reservation are a demonstrated, subeconomic resource at present; the Missouri Valley deposits are far too low in grade to be competitive today. Moreover, a major obstacle to their eventual development is the lack of a proven, efficient, economical method to separate the nodules from the shale or gravel host rock (DeHuff and Jones, 1979, p. 7).

Cobalt, Copper, and Nickel

Unlike some of the manganese-bearing nodules that occur on the sea floor, which have been sought recently for their cobalt, copper, and nickel content, the manganese deposits of the Missouri Valley do not contain significant concentrations of cobalt or nickel (Schlain, 1946; B. H. Clemmons, written commun., 1962). Two spectrographic analyses of the nodules show only 0.01 percent copper (Pesonen and others, 1949, p. 59).

Nonmetallic Mineral Resources

Nonmetallic mineral resources of the Crow Creek Reservation include sand and gravel, clay, and shale. The Niobrara Formation, formerly a source of chalk for building stone, lime, and cement rock in southeastern South Dakota, underlies the reservation. Unfortunately, the most accessible deposits crop out along the Missouri River where they now are covered by the waters of Lake Sharpe and Lake Francis Case. The occurrence of a zeolite mineral (clinoptilolite) may point to a potential resource on the reservation.

Sand and Gravel

Large deposits of sand and gravel occur in terraces along the Missouri River in south-central South Dakota. These terrace deposits consist mostly of glacial outwash material carried by streams from melting glaciers, but some local material, such as manganese-bearing nodules, is present also.

Rothrock (1944a) has compiled an inventory of major sand and gravel deposits along the reach of the Missouri that borders the reservation, and the following data are taken from his report. In addition, the Materials and Tests Laboratory of the Division of Highways, South Dakota Department of Transportation, in Pierre maintains a file of data about sand and gravel deposits used or tested for use by the department. Five large terrace deposits, estimated to contain more than 300 million cubic yards of sand and gravel, lie within the reservation (Figure 1).

The Joe Creek terrace is about 1 mile wide and extends east-west for about 4 miles near the center of T. 108 N., R. 75 W., adjacent to the Missouri River. About 100 million cubic yards of fairly clean sand and gravel is available under little cover.

The Farm Station terrace is directly east of the Joe Creek terrace; it covers about 4 square miles mostly in the southeast part of T. 108 N., R. 74 W. About 150 million cubic yards of fairly clean sand (predominantly) and gravel is present under little cover.

The Soldier Creek terrace lies just northwest of Fort Thompson; it covers about 2¼ square miles near the center of T. 107 N., R. 72 W. Most of the material is of glacial origin, but a fairly large percentage of local material, particularly iron carbonate concretions, is present. Much material from this terrace, originally estimated to contain over 40 million cubic yards of sand and gravel, was used in the construction of Big Bend Dam.

The Fort Thompson terrace is immediately east of Fort Thompson in T. 107 N., R. 71 and 72 W.; it contains about 30 million cubic yards of useable material, mostly sand, under very little cover.

Finally, the large Crow Creek terrace is near the mouths of Crow and Elm Creeks in T. 106 N., R. 71 W., and extends eastward along Crow and Smith Creeks at least to Shelby. Although the deposit contains a large amount of sand and gravel, exceptionally thick cover over much of the deposit, plus a high percentage of iron carbonate and other local material, indicate that most of the sand and gravel is unavailable.

Many factors, such as quality and quantity of the deposit, demand, and especially transportation

costs, would affect the use of sand and gravel resources of the reservation. Existing use of the surface is also an important factor; some of the terrace deposits are within the small part of the reservation now dedicated to irrigated land, a use that may preclude recovery of underlying resources such as sand and gravel.

Clay and Shale

Several investigators have discussed clay and shale resources in the Pierre Shale along the Missouri River in South Dakota, but these resources apparently have not been studied in detail on the reservation. Parts of the Pierre may contain material suitable for making structural clay products or lightweight aggregate.

The USBM investigated clay and shale deposits in North and South Dakota to determine if any were suitable for bloating to make lightweight aggregate (Cole and Zetterstrom, 1954; Zetterstrom and Cole, 1956). They found, as did Karsten (1956), that the Pierre Shale contains suitable material at several of the places tested along the Missouri, including Fort Pierre and Chamberlain; suitable material conceivably may occur on the reservation as well. Because available resources are so large and widespread, potential marketing areas and transportation facilities are perhaps as important as geologic characteristics in locating a lightweight aggregate pit and plant.

Likewise, common clay suitable for making brick, tile, and other structural clay products is widespread and abundant in the State (Rothrock, 1944). It is reported at Pierre and Chamberlain (Patterson and Harksen, 1975, p. 128) and proba-

bly also occurs on the reservation. Again, the chance of developing common clay resources on the reservation, rather than at Pierre where a local market and a good transportation network exist, is remote unless deposits of exceptional quality are found.

Bryson and others (1947) indicate that bentonite crops out above the Pierre-Niobrara contact on the reservation. According to Gries (1942, p. 68), thin beds of bentonite are common in the Sharon Springs Member but seldom exceed 1 foot in thickness. Bentonites in the Pierre are the nonswelling type; such bentonite has been used to filter and purify oils, much like fuller's earth, and to bond foundry sands. Bentonite from the reservation probably cannot compete with similar deposits more favorably situated elsewhere.

Detailed geologic and economic feasibility studies would be needed to determine if clay resources on the reservation can be developed commercially.

Zeolites

Recently, much attention has been directed toward the zeolites because this group of minerals has many new-found industrial and agricultural applications, and substantial deposits of zeolites have been found in certain sedimentary rocks. Zeolites have been reported from several localities in South Dakota, mostly in altered tuffaceous rocks of Tertiary age but also at two sites in the Pierre Shale (Sheppard, 1975, p. 157).

Clinoptilolite, a zeolite mineral, occurs in the Pierre on the reservation both as a minor constituent of no value and as a major component of

certain beds (Schultz and others, 1960, p. 2041). Near the mouth of Crow Creek, 11 miles north of Chamberlain, an altered bed of bentonite is composed almost entirely of clinoptilolite (Schultz, 1963, p. 173). Schultz (oral commun., 1979) found beds of zeolitic bentonite, ranging from less than 1 inch to 10 inches in thickness, at several places along the Missouri River from Little Elm Creek south to the vicinity of Chamberlain.

The economic significance of zeolites on the reservation is not known.

REFERENCES

- Adolphson, D. G., and LeRoux, E. F., 1968, Temperature variations of deep flowing wells in South Dakota, in Geological Survey Research 1968: U. S. Geological Survey Professional Paper 600D, p. D60-D62.
- Bryson, R. P., Fox, E. L., Larrabee, D. M., Weeks, R. A., and Fischer, E. C., 1947, Map showing construction materials and nonmetallic mineral resources of South Dakota: U. S. Geological Survey Missouri Basin Studies No. 12, scale 1:500,000.
- Cole, W. A., and Zetterstrom, J. D., 1954, Investigation of lightweight aggregates of North and South Dakota: U. S. Bureau of Mines Report of Investigations 5065, 43 p.
- Cox, E. J., and others, 1962, Geology of selected highway strips in South Dakota: South Dakota Geological Survey Report of Investigations 93, 153 p.
- Crandell, D. R., 1950, Revision of Pierre Shale of central South Dakota: American Association of Petroleum Geologists Bulletin, v. 34, no. 12, p. 2337-2346. 1958 [1959], Geology of the Pierre area, South Dakota: U. S. Geological Survey Professional Paper 307, 83 p.
- Curtiss, R. E., and Waddel, G. R., 1951, Areal geology of the DeGrey quadrangle: South Dakota Geological Survey Geologic Quadrangle Map, scale 1:62,500. 1951a, Areal geology of the Stephan quadrangle: South Dakota Geological Survey Geologic Quadrangle Map, scale 1:62,500.
- Darton, N. H., 1951, Geologic map of South Dakota: U. S. Geological Survey, scale 1:500,000.
- DeHuff, G. L., and Jones, T. S., 1979, Manganese: U. S. Bureau of Mines Mineral Commodity Profiles, 20 p.
- Dupuy, L. W., Calhoun, W. A., and Rasmussen, R. T. C., 1946, Mining and concentration of Missouri Valley manganese at Chamberlain, South Dakota: U. S. Bureau of Mines Report of Investigations 3839, 103 p.
- Fenneman, N. M., 1931, Physiography of western United States: New York, McGraw-Hill Book Co., Inc., 534 p.
- Flint, R. F., 1955, Pleistocene geology of eastern South Dakota: U. S. Geological Survey Professional Paper 262, 173 p.
- Gries, J. P., 1940, A structural survey of northeastern Stanley County, South Dakota: South Dakota Geological Survey Report of Investigations 34, 52 p., appendix B.
- _____, 1942, Economic possibilities of the Pierre Shale: South Dakota Geological Survey Report of Investigations 43, 79 p.
- _____, 1962, Lower Cretaceous stratigraphy of South Dakota and the eastern edge of the Powder River Basin, in Wyoming Geological Association Guidebook, 17th Annual Field Conference Powder River Basin, 1962, p. 162-172.
- _____, 1975, Manganese, in Mineral and water resources of South Dakota: South Dakota Geological Survey Bulletin 16 (revised), p. 104-108.
- Gries, J. P., and Rothrock, E. P., 1941, Manganese deposits of the lower Missouri Valley in South Dakota: South Dakota Geological Survey Report of Investigations 38, 96 p.

- Henkes, W. C., and Gries, J. P., 1963, Mineral resources and their potential on Indian lands. Crow Creek and Lower Brule Reservations, Buffalo, Hughes, Hyde, Lyman, and Stanley Counties, South Dakota: U. S. Bureau of Mines Missouri River Basin Preliminary Report 151, 42 p. Administrative report on file in Denver library of the United States Bureau of Mines.
- Hewett, D F., 1930, Manganese-iron carbonate near Chamberlain, South Dakota: U. S. Geological Survey Memorandum for the Press, February 5, 1930, 9 p.
- Howells, L. W., 1974, Geohydrology of Crow Creek and Lower Brule Indian Reservations, South Dakota: U. S. Geological Survey Hydrologic Investigations Atlas HA-499, 2 sheets, scale 1:125,000.
- Jacobs, J. H., and Hunter, J. W., 1946, Pilot-plant production of electrolytic manganese from Chamberlain, South Dakota, nodules: U. S. Bureau of Mines Report of Investigations 3862, 14 p.
- Karsten, Andrew, 1956, Characteristics and behavior of certain South Dakota shales under expansion to produce lightweight aggregate: Pierre, South Dakota Natural Resources Commission, 34 p.
- Kepferle, R. C., 1959, Uranium in Sharon Springs member of Pierre Shale, South Dakota and northeastern Nebraska: U. S. Geological Survey Bulletin 1046-R, p. 577-604.
- Knickerbocker, R. G., and Miller, Virgil, 1942, Manganese investigations - metallurgical, 18. Pyrometallurgical studies of manganese ores, Smelting of manganese oxide, carbonate, or silicate ores with copper and iron sulfides: U. S. Bureau of Mines Report of Investigations 3659, 23 p.
- Miller, B. W., 1971, Petroleum potential of South Dakota, in Cram, I. H., ed., Future petroleum provinces of the United States - their geology and potential: American Association of Petroleum Geologists Memoir 15, p. 706-717.
- Miller, R. H., 1959, Mineral resources of South Dakota: Pierre, South Dakota, South Dakota Industrial Development Expansion Agency, 96 p. National Materials Advisory Board, National Research Council, 1976, Manganese recovery technology: NMAB - 323, 81 p.
- Patterson, S. H., and Harksen, J. C., 1975, Clays, bentonite, and lightweight aggregate, in Mineral and water resources of South Dakota: South Dakota Geological Survey Bulletin 16 (revised), p. 125-132.
- Pesonen, P. E., Tullis, E. L., and Zinner, Paul, 1949, Missouri Valley manganese deposits, South Dakota, part I, General investigations, stratigraphic studies, and tonnage and grade estimates: U. S. Bureau of Mines Report of Investigations 4375, 90 p.
- Petroleum Information, (various dates), Well completion cards: Denver, Colorado.
- Petsch, B. C., 1942, The Medicine Butte anticline: South Dakota Geological Survey Report of Investigations 45, 24 p.

- _____, 1946, Geology of the Missouri Valley in South Dakota: South Dakota Geological Survey Report of Investigations 53, 78 p.
- Petsch, B. C., and Fairbanks, Donald, 1952, Areal geology of the Chamberlain quadrangle: South Dakota Geological Survey Geologic Quadrangle Map, scale 1:62,500.
- Petsch, B. C., and others, 1950, Areal geology of the Fort George Butte quadrangle: South Dakota Geological Survey Geologic Quadrangle Map, scale 1:62,500.
- _____, 1950a, Areal geology of the Lower Brule quadrangle: South Dakota Geological Survey Geologic Quadrangle Map, scale 1:62,500.
- Pittsburgh Pacific Company, 1961, Recovery of manganese values from domestic sources--a matter of national concern (An original investigation of large low-grade deposits in South Dakota): 44 p. Unpublished company report on file at Minerals Availability Field Office, U. S. Bureau of Mines, Denver, Colorado.
- Rice, D. D., and Shurr, G. W., 1978, Natural gas resources in shallow, low-permeability reservoirs of northern Great Plains [abs.]: American Association of Petroleum Geologists Bulletin, v. 62, no. 5, p. 891-892.
- _____, 1980, Shallow, low-permeability reservoirs of northern Great Plains-- assessment of their natural gas resources: American Association of Petroleum Geologists Bulletin, v. 64, no. 7, p. 969-987.
- Rothrock, E. P., 1931, A preliminary report on the chalk of eastern South Dakota: South Dakota Geological Survey Report of Investigations 2, p. 47-51.
- _____, 1943, Missouri Valley manganese deposits between Lower Brule and DeGrey: South Dakota Geological Survey Report of Investigations 46, 66 p.
- _____, 1944, A geology of South Dakota, part 3, Mineral resources: South Dakota Geological Survey Bulletin 15, 255 p.
- _____, 1944a, Sand and gravel deposits in the Missouri Valley between Little Bend and White River: South Dakota Geological Survey Report of Investigations 47, 118 p.
- Schlain, David, 1946, Cobalt content of manganese ores, pt. 1 of Recovery of cobalt from manganese ores in the production of electrolytic manganese: U. S. Bureau of Mines Report of Investigations 3866, p. 2-12.
- Scholle, Peter, 1978, Diagenesis and hydrocarbon potential of Upper Cretaceous chalks of Western Interior [abs.]: American Association of Petroleum Geologists Bulletin, v. 62, no. 5, p. 892.
- Schoon, R. A., and McGregor, D. J., 1974, Geothermal potentials in South Dakota: South Dakota Geological Survey Report of Investigations 110, 76 p.
- Schultz, L. G., 1963, Nonmontmorillonitic composition of some bentonite beds, in Proceedings of the eleventh national conference on clays and clay minerals, Ottawa, Canada, August 13-17, 1962: Clays and Clay Minerals, y. 11, p. 169-177.
- Schultz, L. G., Tourtelot, H. A., and Gill, J. R., 1960, Mineralogy of the Pierre Shale (Upper Cretaceous) in South Dakota and adjacent areas [abs.]: Geological Society of America Bulletin, v. 71, no. 12, pt. 2, p. 2041.

- Searight, W. V., 1937, Lithologic stratigraphy of the Pierre Formation of the Missouri Valley in South Dakota: South Dakota Geological Survey Report of Investigations 27, 63 p.
- Sheppard, R. A., 1975, Zeolites, in Mineral and water resources of South Dakota: South Dakota Geological Survey Bulletin 16 (revised), p. 155-157.
- Shurr, G. W., and Rice, D. D., 1979, Stratigraphic studies of the Upper Cretaceous in eastern North and South Dakota [abs.]: Geological Society of America Abstracts with Programs, v. 11, no. 5, p. 256.
- Steece, F. V., 1975, Structural geology outside of the Black Hills, in Mineral and water resources of South Dakota: South Dakota Geological Survey Bulletin 16 (revised), p. 50, fig. 11.
- Swanson, V. E., 1960, Oil yield and uranium content of black shales: U. S. Geological Survey Professional Paper 356-A, p. 1-44.
- Torgeson, D. R., Evans, T. E., Morning, J. L., Wessel, F. W., and Knickerbocker, R. G., 1946, Pilot-plant investigations, matte smelting of Chamberlain, South Dakota, manganese ore: U. S. Bureau of Mines Report of Investigations 3917, 47 p.
- Tourtlot, H. A., 1956, Radioactivity and uranium content of some Cretaceous shales, Central Great Plains: American Association of Petroleum Geologists Bulletin, v. 40, p. 62-83.
- U. S. Bureau of Indian Affairs, 1979, Annual report of caseloads, acreages under BIA and surface leasing, September 30, 1979; Crow Creek Reservation, South Dakota: Aberdeen, South Dakota, 2 p.
- U. S. Bureau of Indian Affairs, 1979a, Annual report of mineral leasing activities, September 30, 1979, Crow Creek Reservation, South Dakota: Aberdeen, South Dakota, 2 p.
- U. S. Bureau of Mines and U. S. Geological Survey, 1980, Principles of a resource/reserve classification for minerals: U. S. Geological Survey Circular 831, 5 p.
- Wing, M. E., and Gries, J. P., 1941, Stratigraphy and structure of the Chamberlain section of the Missouri River Valley: South Dakota Geological Survey Report of Investigations 39, 68 p.
- Zetterstrom, J. D., and Cole, W. A., 1956, Expansion of clays and shales from North and South Dakota in a rotary kiln: U. S. Bureau of Mines Report of Investigations 5202, 13 p.
- Zinner, Paul, and Grosh, W. A., 1949, Missouri Valley manganese deposits, South Dakota, part III, Mining and beneficiation studies: U. S. Bureau of Mines Report of Investigations 4429, 56 p.




Figure 1. Map of the Crow Creek Indian Reservation, South Dakota, showing manganese and sand and gravel resources (mineral resource data from Pesonen and others, 1949; and Rothrock, 1944a).

YANKTON




Figure 2. Index to topographic and geologic mapping, Crow Creek Indian Reservation, South Dakota.




Figure 3. Major structural features of South Dakota. Map adapted from Wing and Gries (1941), Rothrock (1944), Petsch (1946), and Steece (1975).

